BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT1353

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/13/2023-24, Date: 26-12-2023

Name of Work: Removal of silt & Repair and maintenance of footpath in new ward no.14 Kuvempunagara.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRADEEPA K A	
				In Figures	In Words
1	486.00	Removing and resetting of footpath slab	Sqm	235.00	Rupees Two Hundred Thirty Five Only
2	344.25	Removing and resetting stone slabs of drains and pointing in C.M (1:3)	Sqm	121.00	Rupees One Hundred Twenty One Only
3	216.00	Supply of Hydraulic Excavator of 0.9 m3 bucket on hire basis including operator, fuel and other incidental charges etc., complete	hr	1350.00	Rupees One Thousand Three Hundred Fifty Only
4	1440.00	Supply of Tipper-5.5 m3 on hire basis including operator, fuel and other incidental charges etc., complete	hr	1390.00	Rupees One Thousand Three Hundred Ninety Only
5	203.40	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drain age of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.	Sqm	1200.00	Rupees One Thousand Two Hundred Only
6	13.50	Supplying and fixing Pre cast reinforced concrete slab 23cm thick including cost of reinforcement as per design and drawing courses cost of all materials, labour complete as per specifications.	Sqm	5037.00	Rupees Five Thousand Thirty Seven Only
7	31.50	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:2:4 Using 20 mm nominal size graded crushed coarse aggregate	Cum	6840.00	Rupees Six Thousand Eight Hundred Forty Only
8	1.00	Supply of Material component Bitumen (emulsion) Rapid Setting RS1* for all road works.	t	43000.00	Rupees Forty Three Thousand Only
9	300.00	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2800.00	Rupees Two Thousand Eight Hundred Only
10	1728.00	Supply of Unskilled Mazdoor Heavy Labours As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	643.40	Rupees Six Hundred Forty Three and Forty Paise Only
11	288.00	Supply of Skilled Mason or Brick layer Class-1 As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	676.67	Rupees Six Hundred Seventy Six and Sixty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike

Executive Engineer
Byarayanapura Division
BBMP, Bangalore-92